

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rooks County. Sec. 33 Twp. 10S Rge. 20 (E) W (W)
Location as "NE/CNW/SW" or footage from lines 1320' from North and 440'
Lease Owner Continental Oil Company from West lines
Lease Name C. E. Allphin Well No. 3
Office Address Drawer 98 - Plainville, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Test
Date well completed May 21, 19 53
Application for plugging filed April 16, 19 58
Application for plugging approved April 18, 19 58
Plugging commenced May 20, 19 58
Plugging completed May 21, 19 58
Reason for abandonment of well or producing formation Field Test Completed
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation None Depth to top Bottom Total Depth of Well 3,840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	263'	None
				5 1/2"	2,336'	2,336'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole and found it open. Pumped in 12 sacks of mud to load the hole. Pulled 67 joints and pumped in 20 sacks of cement to 500'. Pulled 9 joints and pumped in 20 sacks of cement to 240'. Pulled the rest of the casing (9 joints), cleared hole and checked the fluid to 40'. Mudded to 30' and ran 10 sacks of cement to the base of the cellar.

6-2-1958

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS COUNTY OF ROOKS, ss.
L. E. Powell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. E. Powell

Drawer 98 - Plainville, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of May, 19 58

My commission expires December 2, 1961

[Signature]
Notary Public.

State Corp. Comm.
RFD
File

PLUGGING
FILE SEC 33 T. 10 20W
BOOK PAGE 24 LINE 10