

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Rooks County. Sec. 33 Twp. 10S Rge. (E) 20(W)  
Location as "NE/CNW/SW" or footage from lines. 1650'FW & 330'FN lines of  
Lease Owner Continental Oil Company  
Lease Name C. E. Allphin Well No. 9  
Office Address Drawer 367, Plainville, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-13 19 60  
Application for plugging filed (Verbal) 6-22 19 62  
Application for plugging approved 6-22 19 62  
Plugging commenced 6-26 19 62  
Plugging completed 6-27 19 62  
Reason for abandonment of well or producing formation  
Casing experiment completed.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
Producing formation None Depth to top Bottom Total Depth of Well 2076 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	221'	None
				5 1/2"	2044'	2044'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Pulled 62 joints of 5 1/2" casing. Ran 500' of  
2" tubing and pumped in 8 sacks of jel and  
20 sacks of cement. Pulled 10 joints of 2" tubing  
and pumped in 20 sacks of cement. Pulled 6 joints  
of tubing, checked fluid at 30' and filled to  
base of cellar with 10 sacks of cement.

RECEIVED  
JUL 2 1962  
7-20-1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rooks, ss.  
L. E. Powell (employee of owner) or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.  
ARC  
State Corp. Comm. (Signature) L. E. Powell  
CRW Drawer 367, Plainville, Kansas  
File (Address)  
SUBSCRIBED AND SWORN TO before me this 17th day of July, 19 62

My commission expires 12-2-65 Kenneth J. Query Notary Public.