

15-195-20217-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Trego County, Sec. 34 Twp. 12 Rge. 21 (E) (W)

Location as "NE/CNW/KSW" or footage from lines NW NW NE
Lease Owner Specter Pipe & Supply
Lease Name Merrill #1 Well No. _____
Office Address Russell, Kansas 67665
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed June 7, 1972 19____
Application for plugging filed June 27, 1973 19____
Application for plugging approved June 29, 1973 19____
Plugging commenced 7/6/73 19____
Plugging completed 7/9/73 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation Arbuckle Depth to top 3877 Bottom 3880 Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	215	none
				4 1/2"	3876	2945'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 3600' and ran 10' of sand and 4 sacks cement.
Loaded hole, shot pipe at 3092', 2958', pulled 91 joints of 4 1/2" casing.
Allied squeezed well with 5 sacks hulls, 25 sacks gel and 150 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
07-16-1973
JUL 16 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of July, 1973

My commission expires _____

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

15-195-20217-00-00

DRILLERS LOG

No. 1 Merrill

CASING RECORD:	COMPANY: Hershberger Explorations Inc.	DESCRIPTION:
8 5/8" @ 215' w/150 sx cement	CONTRACTOR: Red Tiger Drilling Company	NW NW NE 34-12S-21W
4 1/2" @ 3876' w/150 sx cement	COMMENCED: May 27, 1972	Trego County, Kansas
TOTAL DEPTH: 3880'	COMPLETED: June 7, 1972	ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Foot Rock & Shale	0	225	
Shale	225	370	
Shale & Sand Strks	370	1080	
Sand	1080	1290	
Shale	1290	1575	
Anhydrite	1575	1617	
Shale	1617	1660	
Shale & Lime	1660	2225	
Lime	2225	3877	
Arbuckle	3877	3880	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jim Farrice
Jim Farrice

Subscribed and sworn to before me this 12th day of June, 1972.



Virginia K. Acheet
Notary Public

My Commission Expires:
7-23-74

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1973
07-05-1973
CONSERVATION DIVISION
Wichita, Kansas