


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

15-195-00108-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Trego County. Sec. 34 Twp. 12S Rge. 21W (W)
 Location as "NE/CNW/SW" or footage from lines SE 1/4 SW 1/4 NE 1/4
 Lease Owner Arnell Company & Leben Drilling, Inc.
 Lease Name Merrill "A" Well No. 1
 Office Address 533 Petroleum Bldg., Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed 1-15-69 19
 Application for plugging filed 1-15-59 19
 Application for plugging approved 1-15-59 19
 Plugging commenced 1-15-59 19
 Plugging completed 1-15-59 19
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -- 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fabricius
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	259'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 650' w/20 sacks cement
 Set 2nd plug @ 240' w/20 sacks cement,
 top plug @ 40' w/10 sacks cement to base of cellar.

RECEIVED
 STATE CORPORATION COMMISSION
 01-27-1959
 JAN 27 1959
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Leben Drilling, Inc.
 Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James M. Battin, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Battin
905 Central Bldg., Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of January, 19 59

Ruth N. Benjamin
 Ruth N. Benjamin Notary Public.

My commission expires June 17, 1961

PLUGGING
 FILE SEC 34T. 12 R. 21W
 BOOK PAGE 12 LINE 38

15-195-00108-00-00

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

ARTNELL COMPANY & LEBEN DRILLING, INC.
LEBEN DRILLING, INC.
MERRILL "A" #1
SE 1/4 SW 1/4 NE 1/4 SEC. 34-12S-21W
TREGO COUNTY, KANSAS
JANUARY 4, 1959
JANUARY 15, 1959

0	40	Clay		
40	259	Shale & Shells		
259	1015	Shale, Sand & Shells		
1015	1075	Sand	<u>TOPS:</u>	
1075	1300	Sand	Anhydrite	1585
1300	1585	Shale & Redbed	Topeka	3270
1585	1628	Anhydrite	Heebner	3478
1628	1865	Shale & Lime	Toronto	3502
1865	2150	Shale & Shells	Lansing	3513
2150	2770	Lime & Shale	Base K.C.	3754
2770	3513	Lime & Shale	Marmaton Ch.	3818
3513	3565	Lime	Arbuckle	3907
3565	3615	Lime & Shale		
3615	3761	Lime	Elevation	2225 K.B.
3761	3810	Shale & Lime		
3810	3845	Shale & Lime(Cherty)		
3845	3880	Chert		
3880	3907	Conglomerate		
3907	3920	Dolomite		
	3920	Rotary Total Depth - D & A		

Set 259' of 8 5/8" surface casing with 150 sacks cement with 2% CaCl.

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Merrill "A" #1, located SE 1/4 SW 1/4 NE 1/4 of Section 34, Township 12 South, Range 21 West, Trego County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: *James M. Battin*
James M. Battin

STATE OF KANSAS) ss:
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 19th day of January, 1959.

Ruth H. Benjamin
Ruth H. Benjamin, Notary Public

My commission expires:
June 17, 1961

JAL
COR. 01-27-1959

34 12 21W
12 1/2 E 38