

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#4

API NUMBER 15-195-21,453-00-00

LEASE NAME Seitz/Barnhart "A"

WELL NUMBER 1

4,290 Ft. from S Section Line

2,970 Ft. from E Section Line

SEC. 34 TWP. 12 RGE. 21 ~~W~~ or (W)

COUNTY Trego

Date Well Completed 5-30-84

Plugging Commenced 12:45 1-13-89

Plugging Completed 1:30 1-13-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Glenn D. Diehl Oil Operations

ADDRESS P. O. Box 234

PHONE#(913) 625-6711 OPERATORS LICENSE NO. 09346

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? #4 - Hays

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3902 Bottom 3924 T.D. 3924

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	259	8-5/8"	259	0
		0	3921	5 1/2"	3921	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
8-5/8" backside could not pump into @ 500# max. psi. Pump into 5 1/2" casing
300 sx 60/40 poz 6% gel, NO calcium chloride, with 5 sacks hulls @ 300# max
psi. Shut well in @ 150# psi.

RECEIVED
STATE CORPORATION COMMISSION
01-17-1989

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. JAN 17 1989

Address Box 31, Russell, Kansas 661

STATE OF Kansas COUNTY OF Ellis, ss.

CONSERVATION DIVISION
Wichita Kansas

Glenn D. Diehl (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Glenn D. Diehl

(Address) P. O. Box 234, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this
NOTARY PUBLIC
STATE OF KANSAS
My Comm. Expires

16th day of January, 19 89

Robert E. Diehl
Notary Public

My Commission Expires: 8-27-89