

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 28 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Morgan of Aspen Drlg. has this date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Aspen Resources LTD

Complete Address: 710 One Twenty Bldg., Wichita, Kansas

Lease Name: Shuts Well No. 1

Location: SW NW NW Sec. 33 Twp. 12 Rge. (E)(W) 20

County: Ellis Total Depth 3865 Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Morgan was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 660' and displace  
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo Z. Massey  
Conservation Division Agent