

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. - 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Musgrove of Hellar Drlg. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Winwell 1968 Exploration Company

Complete Address: 1011 Coml. Nat'l Bank Bldg., Shreveport, Louisiana

Lease Name: Schwägel "A" Well No. 1

Location: SW NW NE Sec. 36 Twp. 12 Rge. 20 (E)(W) X

County: Ellis Total Depth 3495 Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Musgrove was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Geo F. Massey  
Conservation Division Agent