

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Blu Westnett of Champlin Petroleum Co. has this date requested permission to plug the following described well:

Operator's Full Name: Champlin Petroleum Co.

Complete Address: Box 9345 - Ft. Worth Texas 76107

Lease Name: Rogers B' Well No. B-2

Location: NE-NE-NE Sec. 23 Twp. 10 Rge. 20 (E) (W)

County: Roos Total Depth: 3765

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Westnett was instructed to plug the well as follows:

8 5/8" @ 207' w/165 sk common / 5 1/2" @ 3759' w/100 sk
Open hole - 3759-65 - 2 7/8" tbg set on Pbr. @ 3727'
(Pbr stuck) - Hole in Dakota @ 1245 - Hole in tbg @ 2800'
Ordered 400 sk .50/50 prog 6% gel - 6 hulls - Pumped in
2 7/8" .100 sk cmt + 2 hulls PSI. 200# Shut in
8 5/8" 100 sk cmt + 2 hulls PSI 150# Shut in
5 1/2" 200 sk cmt + 2 hulls PSI 200# Shut in

Very truly yours,

Dennis L. Hamel
Conservation Division Agent

STATE CORPORATION COMMISSION
RECEIVED
9-14-1982
SEP 14 1982
CONSERVATION DIVISION
Wichita, Kansas