



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1966
01-03-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

15-195-30098-00-00

Dear Sir:

Mr. Darrell Kelso of Knight Casing Pulling Co. has this

date requested permission to plug the following described well:

Clinton Oil Co.

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company,

Complete Address: 6810 W. Hwy. US 54, Wichita, Kansas.

Lease Name: Blakely Well No. 1-X

Location: CS/1/2-NW-NE Sec. 29 Twp. 12 Rge. (E) (W) 21

County Trego Total Depth 3955 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

248'--8 5/8" Surface pipe, cement circulated
3954'--5 1/4" Production casing cemented with 125 Sx. Top of
cement @ 3452' (Temperature Survey). Well plugged back to
3935'. Top perforations @ 3582'.
Push plug to 3550, sand back to 3540' and set 5 Sx. cement
with dump bailer. If hole will bail to 400', set rock bridge
and dump 6 yards Redi-Mix concrete to bottom of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent