

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

01-03-1972

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-195-30129-00-00

Operator's Full Name Braden-Deem, Incorporated,

Complete Address 200 East First, Wichita, Kansas.

Lease Name Merrill Well No. 1

Location CS/2-NE-NW Sec. 34 Twp. 12 Rge. (E) (W) 21

County Trego Total Depth 3909'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 5:00 PM Day 30 Month 12 Year 1971

The above well was plugged as follows:

112'--10 3/4" Surface casing, cement circulated with 120 Sx.
1660'--7" OD Intermediate string casing, cement circulated with 400 Sx.
3898'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to
3880'. Top of perforations @ 3852'.

Sanded well back to 3840' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and set rock bridge @ 900' and filled hole from 900' to 550' with 3 yards Redi-Mix
cement. Filled hole from 550' to 250' set rock bridge and then 2 yards Redi-Mix
cement from 250' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-7-72
INV. NO. 4880-4

Signed: K. L. Dickel
Well Plugging Supervisor