

6P 57

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1972
CONSERVATION DIVISION
Wichita, Kansas

15-195-00479-00-00

01-17-1972

Operator's Full Name Braden-Deem, Incorporated,

Complete Address 200 East First, Wichita, Kansas.

Lease Name Merrill Well No. 1

Location NE-NE-NW Sec. 34 Twp. 12 Rge. (E) (W)21

County Trego Total Depth 3883'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated This well was formerly abandoned, plugged and 5 1/2" casing pulled from 1000'. Attempt to get in 5 1/2" to rework well resulted in failure.
Plugging Contractor Allied Cementing Company, Incorporated,

Address Box # 207, Russell, Kansas. License No.

Operation Completed: Hour 3:15 PM Day 12 Month 1 Year 1972

The above well was plugged as follows:

234'--8 5/8" Surface casing, cement circulated with 135 Sx.
3883'--5 1/2" Production casing cemented on bottom with top of perforations @ 3871'. It is assumed bottom was plugged off properly when well was plugged initially.

Squeezed well initially with 2 sacks hulls and 13 sacks gel and followed with 110 Cu. Ft. cement from 900' to 550' then 8 sacks gel from 550' to 250' and followed with 30 Cu. Ft. cement from 250' to 175' then 4 sacks gel from 175' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-250#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-17-72

INV. NO. 5016-W