

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-195-20217-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 11 1973  
07-11-1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Specter Pipe and Supply, Incorporated,

Complete Address Box #169, Russell, Kansas.

Lease Name Merrill Well No. 1

Location NW-NW-NE Sec. 34 Twp. 12 Rge. (E) (W) 21

County Trego Total Depth 3880'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 12:30 PM Day 9 Month 7 Year 1973

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3876'--4 1/2" Production casing cemented on bottom with 150 Sx.

Pushed plug to 3600', sanded back from 3600' to 3590' and set 4 Sx. cement with dump  
bailer. Pulled 4 1/2" casing (2900') and squeezed well initially with 5 sacks hulls  
and 18 sacks gel and followed with 110 Cu. Ft. cement from 725' to 400' then 4 sacks  
gel from 400' to 240' and followed with 30 Cu. Ft. cement from 240' to 165' then 3  
sacks gel from 165' to 45' and finally 10 Cu. Ft. cement from 45' to bottom of cellar.

Maximum pump-in pressure-500#. Final shut-in pressure-200#. (Mudding and Cementing by  
Allied Cementing Company, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 7/13/73

INV. NO. 7620-W