

KANSAS

Form CP-3
Rev. 6-26-62

74

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-195-20084-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Company,

Complete Address: 410 Fourth National Bank Building, Wichita, Kansas.

Lease Name Merrill Well No. 1

Location E/2-SW-NW Sec. 34 Twp. 12 Rge. (E) (W) 21

County Trego Total Depth 3936

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Dunn-Gardner Drilling Company, Incorporated,

Address: 300 Schweiter Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 3:45 PM Day 24 Month 8 Year 1968

The Above well was plugged as follows:

140'--8 5/8" Surface casing, cement circulated ~~by~~ with 125 Sx.
Top of Dakota section @ 585'.

Circulated hole with heavy mud. Pulled DP to 810' and displaced 100 Sx. cement thru
DP from 810' to 490'. Pulled DP to 155' and displaced 20 Sx. cement thru DP from 155'
to 95'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/27/68
8362-u
INV. NO. _____

Signed: *M. R. Nichols*
Well Plugging Supervisor