

15-163-12500-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 7 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Chester Williams & D & D Drg Co

Complete Address: 419 1st Natl Bk Bldg Wichita, Kans

Lease Name Briggs Well No. 2

Location CN $\frac{1}{2}$  NE NW Sec. 34 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3690

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A x

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: D & D Drg Co & Halliburton Co

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 8AM Day 4 Month 6 Year 63

The Above well was plugged as follows:

8 5/8" 201' circulated with cement.

Circulated hole with heavy mud, set plug at 550', displaced 20 sax

cement through drill pipe, heavy mud to 190', set plug and 20 sax

cement displaced through drill pipe, heavy mud to 40', set plug,

hulls and filled to bottom cellar with cement.

Cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 6/14/63  
INV. NO. 4224-44

Signed:

Redon Peely  
Well Plugging Supervisor