

15-163-01060-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*AD*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

JUL 19 1972

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas 67202

Lease Name Harlan Well No. 1

Location S/2 NW SW Sec. 34 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3773'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12 N Day 18 Month 7 Year 1972

The above well was plugged as follows:

Total Depth 3773' 8 5/8 csg set at 240' cwc 175 sk. Cmt. Mat, reg. poz 6% gel

4 1/2 csg set at 3772' cw 200 sk cmt.

4 1/2 csg top perf. (3534')

Set 4 1/2 wood plug at 3500' -poured 10' sd -dumped 4 sk cmt W/dump bailer. (3455-3500)

Cutoff and recovered 1365' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls, -70 sk cmt -12 sk

gel & water -released 8 5/8 plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. A. Mansley*  
Well Plugging Supervisor

INVOICED

DATE 7/19/72

INV. NO. 6049-U