

15-163-20632-0000

KANSAS

Form CP-3

Rev. 6-4-68

RECEIVED

STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 04 1976

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

CONSERVATION DIVISION  
Wichita, Kansas  
API # 15-163-20,632

Operator's Full Name Thornton E. Anderson  
Complete Address Suite 746, 300 W. Douglas, Wichita, Kansas  
Lease Name Harlan Well No. 1  
Location W/2 NW NE SW Sec. 34 Twp. 10 Rge. (E) (W) 20  
County Rooks Total Depth 3731  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Rains & Williamson Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 2:45 P Day 1 Month 10 Year 1976

The above well was plugged as follows:

RTD 3731' 8 5/8 csg set 257' cwc 150 sx. Plg. Mat. 50-50 poz 6%  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.  
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Murray  
Well Plugging Supervisor

INVOICED

DATE 10-5-76

INV. NO. 3928-W