

15-163-00951-0000

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rooks

Location: SE NE NW Sec. 34 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 20

Name of Field: \_\_\_\_\_ Total Depth: 3712

I have this date completed supervision of plugging of:

Lease Name: Briggs Well No. X<sup>2</sup>

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Plugging Contractor Pipe Pullers Inc

Address: Great Bend, Kans License No. 462

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?  
Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1961  
CONSERVATION DIVISION  
Wichita, Kansas

Operation Completed: Hour 2:30PM Day 27 Month 10 Year 61

The above well was plugged as follows:

8 5/8" 168' circulated with cement - 5 1/2" 3712' with 150 sax cement.

PB to 3475' - perforated 3459'

Filled with sand to 3390', set 4 sax cement with dump bailer - pulled

2705' 5 1/2" to 550' - circulated hole with heavy mud through 5 1/2" ( 27 sax Gel)

displaced 20 sax cement through 5 1/2" at 550' - heavy mud to 180' - displaced

20 sax cement through 5 1/2" at 180' - heavy mud to 35', set bridge and 10

sax cement to bottom cellar.

Mudding and cementing by Pipe Pullers pump truck.

Signed: Leon Petty  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED  
DATE 11/9/61  
INV. NO. 4014-W