

15-163-20638-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

NOV 14 1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Thornton E. Anderson

Complete Address 300 W. Douglas, Suite 746, Wichita, Kansas 67202

Lease Name Briggs Well No. 1

Location SW NE NW Sec. 34 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3678'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1 P Day 9 Month 11 Year 1977

The above well was plugged as follows:

Total Depth 3678' 8 5/8 csg set 268' cwc 200 sk.

4 1/2 csg set 3677' cw 150 sk cem. PFS (3676-3677)

Filled 4 1/2 csg with sand (3678'-3650') dumped 3 sk cem W/dump bailer. (3650'-3620')

Cutoff & recovered 2605' of 4 1/2 csg.

Allied Cementing Co. Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs

Hulls. followed with 70 sk 50-50 poz 6% -displaced with 8 sk gel & water & capped

with cementing plug & 70 sk 50-50 poz 6% & shutin. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-14-77

INV. NO. 6191-W

Signed: Geo Massey
Well Plugging Supervisor