


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SW

SEC. 3 TWP. 10 RGE. 21

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Miller

Operator Anderson - Prichard Address 314 Orpheum Bldg
Wichita, Kans

Field _____ County Graham

Total Depth 3829 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 244' circulated with cement - 5 1/2" at 3827'
with 125 sax cement behind - Lane Wells plug at 3700'-
Retainer plug at 1150'- Squeezed at 1205' with 300 sax cement
tools lost in hole at 1150' - Pulled 610' 5 1/2" casing -
filled hole with mud to 240', set rock bridge and 20 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 3 TWP 10 RGE 21
BOOK PAGE 19 LINE 13
MAY 23 1952
CONSERVATION DIVISION
Wichita, Kansas

Edwin Ledy
District Conservation Agent
Date 5-24-52