

15-065-01682-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*pl*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company,

Complete Address Box #287, Great Bend, Kansas.

Lease Name Morel Well No. 2

Location NW-SW-SE Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3869'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 2:30 PM Day 7 Month 2 Year 1973

The above well was plugged as follows:

1830'--8 5/8" Surface casing, cement circulated with 1050 Sx.  
3860'--5 1/2" Production casing cemented on bottom with 200 Sx. (Open Hole Completion).

Sanded well back to 3850' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(2750'). Checked fluid level @ 400'. Squeezed well initially with 3 sacks hulls and  
15 sacks gel then 130 Cu. Ft. cement from 1000' to 625' then 15 Sacks gel from 625 to  
25' and finally 20 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in press-  
ure-500#. Final shut-in pressure-200#. (Mudding and Cementing by Allied Cmtg., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: K. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 2/12/73  
INV. NO. 6958-W