

15-065-01007-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum, Incorporated.

Complete Address: Drawer "D", Great Bend, Kansas.

Lease Name C. L. Miller Well No. 4

Location NE-SE-SW Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3852

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Forbes Casing Pulling, Incorporated.

Address: Box #221, Great Bend, Kansas License No. 49

Operation Completed: Hour 9:00AM Day 13 Month 6 Year 1964

The Above well was plugged as follows:

265' --8 5/8" Surface pipe, cement circulated.  
3851.5' 5 1/2" production casing cemented with 125 Sx. 5 1/2" squeezed @ 500'.

Sanded well back to 3820' and set 4 Sx. cement with dump bailer.  
Recovered 8 joints of Range 2 production casing. Set 10' rock bridge @  
260' and ran 20 Sx. cement. Heavy mud to 40', set 10' rock bridge and  
10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. D. Dinkel  
Well Plugging Supervisor

DATE 6/17/64  
INV. NO. 9331-W