

15-065-01683-0000  
1

Form CP-3  
Rev. 6-4-68

*AL*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 4 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Phillips Petroleum Company,

Complete Address Box # 287, Great Bend, Kansas.

Lease Name Morel Well No. 3

Location SW-SW-SE Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham RTD Total Depth 3858

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #105, Chase, Kansas. License No. 6211

Operation Completed: Hour 1:00 PM Day 2 Month 11 Year 1969

The above well was plugged as follows:

1811'--8 5/8" Surface casing, cement circulated with 955 Sx.

3850'--5 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to

3795'. Top of perforations @ 3517'. Fluid level @ 925' before starting to squeeze.

Pushed plug to 3100', sanded back to 3350' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 35 sacks gel from 1600' to 200'

and followed with 60 Sx. cement from 200' to bottom of cellar. Maximum pump-in press-

ure--300#. Final shut-in pressure--100#. (Recovered 2511'--5 1/2" casing).

(Mudding and cementing operations performed by Allied Cementing Co., Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichel*  
Well Plugging Supervisor

DATE 4/4/69  
INV. NO. 9547-W