

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 23 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name Tribble Well No. 3

Location RT-CC SW NE-NE-NE Sec. 5 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3632

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 599

Operation Completed: Hour 12:00M Day 19 Month 5 Year 1966

The Above well was plugged as follows:

1634'--8 5/8" Surface pipe, cement circulated,  
3821'--5 1/2" Production casing cemented with 200 Sx.. Well plugged back  
to 3632'. Top perforations from 3502' to 3508'.

Sanded well back to 3480' and set 5 Sx. cement with dump bailer to 3440'.

Found top of fluid @ 500', set rock bridge and 25 Sx. cement to 425'.

Filled with mud from 425' to 30' and 10 Sx. cement to bottom of cellar.

(Recovered 2522'--5 1/2" Casing)

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 5/23/66

INV. NO. 3258-4