

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 19 1967  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Phillips Petroleum Company,

Complete Address: Box #287, Great Bend, Kansas.

Lease Name Tribble Well No. 1

Location NE-NE-NE Sec. 3 Twp. 10 Rge. (E) (W)21

County Graham Total Depth 3861'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 6:00PM Day 14 Month 6 Year 1967

The Above well was plugged as follows:

1479'--8 5/8" Surface pipe, cement circulated with 1050 Sx.  
3848'--5 1/2" Production casing cemented with 200 Sx. Well plugged back to  
3445'. Top perforations @ 3309'.

Pushed plug to 3290', sanded back to 3275' and set 5 Sx. cement with dump  
Bailer. Pulled 5 1/2" casing. Set 10' rock bridge @ 1479' and set 10 Sx.  
cement on top of bridge. Build 10' rock bridge @ 500' and set 10 Sx.  
cement on top of bridge. Filled hole with mud to 40', set 10' rock bridge  
and 10 Sx. cement to bottom of cellar. (Recovered 2997' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dehala  
Well Plugging Supervisor

INVOICED  
DATE 6/19/67  
INV. NO. 5429-u