

15-065-02409-0000

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 92-29

LOCATION CW $\frac{1}{2}$  SE SE

SEC. 3 TWP. 10 RGE. 21

Dry Hole x Abandoned Oil Well          Abandoned Gas Well         

I have today completed supervision of plugging of:

Well No. 4 Lease Morel

Operator Phillips Pet Co Address Box 779 Gret Bend, Kans

Field          County Graham

Total Depth 3898 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1772' circulated with 1050 sax cement -

5 1/2" at 3868' with 200 sax behind - Baker plugs to

3725' - top perforations at 3541' -

Filled with sand and chat to 3530', set 4 sax cement with dump

bailer, pulled 2556' 5 1/2", filled hole with mud to 250', set

rock bridge and 15 sax cement, filled with mud to 35', set

rock and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 23 1951

*Edna Scott*  
District Conservation Agent

Date 7-17-51

**PLUGGING**  
FILE SEC 3 T 10 R 21  
BOOK PAGE 92 LINE 29