

15-065-01681-0000

Form CP-3
Rev. 6-4-68

~~KANSAS~~

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company,

Complete Address P. O. Box #287, Great Bend, Kansas.

Lease Name Morel Well No. 1

Location 330' FSL & 330' FEL of SE/4 Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address P. O. Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 5:00 PM Day 26 Month 11 Year 1974

The above well was plugged as follows:

1880'--8 5/8" Surface casing, cement circulated with 1100 Sx.
3859'--5 1/2" Production casing cemented on bottom with 150 Sx. (Open Hole Completion).

Sanded well back to 3840' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(2705') and squeezed well initially with 5 sacks hulls and 13 sacks gel following
with 225'Cu. Ft. cement then 12 sacks gel and finally 25 Cu. Ft. cement. Maximum
pump-in pressure-500#. Final shut-in pressure-200#. (Mudding and cementing by Allied
Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/4/74
INV. NO. 394-W