

15-065-01680-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JAN 2 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rocket-Schusterman Oil Account,

Complete Address 1209 Mid-Continent Building, Tulsa, Oklahoma.

Lease Name Miller Well No. 11

Location NE-NW-SW Sec. 3 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Allied Cementing Company, Incorporated,

Address Box #207, Russell, Kansas. License No. _____

Operation Completed: Hour 3:30 PM Day 27 Month 12 Year 1973

The above well was plugged as follows:

194'--8 5/8" Surface casing, cement circulated with 150 Sx.

3864'--5 1/2" Production casing cemented on bottom. No plug back nor perforations indicated. Stage collar set @ 1786' with cement circulated to surface.

Squeezed 5 1/2" casing with 1 sack hulls and 25 sacks cement, encountered 1500# pressure.

Followed with 60 Sx. cement, slowly. Maximum pump-in pressure-1500#. Final shut-in

pressure-1500#. Pressured annulus to 500# with no leakage.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 1/4/74
INV. NO. 8360-W