

15-163-20411-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*E*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 4 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corporation

Complete Address 1000 Century Plaza Wichita, Kansas

Lease Name Thomas Well No. 1

Location SE NW SW Sec. 21 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3475'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Dreiling & Sons

Address Victoria, Kansas License No.       

Operation Completed: Hour 2:45 P Day 30 Month 12 Year 1971

The above well was plugged as follows:

RTD 3475' 8 5/8 csg set at 233' cwc. Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 220' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4968-W