

15-163-20634-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION
Wichita, Kansas
(for this well)

Operator's Full Name Earl M. Knighton

Complete Address 710 Petroleum Bldg., Wichita, Kansas 67202

Lease Name Schonthaler Well No. 1

Location E/2 SE NW Sec. 21 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3764'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 9 Month 11 Year 1977

The above well was plugged as follows:

Total Depth 3764' 8 5/8 csg set 292' cwc 175 sk.

4 1/2 csg set 3762' cw 175 sk cem. Top perf. (3260')

Set 4 1/2 wood plug at 3200' -poured 25' sand-dumped 3 sk cem W/dump bailer. (3200'-3150')

Cutoff & recovered 2813' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs

hulls, followed with 70 sk 50-50 poz 6% -displaced with 8 sk gel & water & capped

with cementing plug & 70 sk 50-50 poz 6% & shutin. FPP 350 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11-14-77

INV. NO. 6190-W

Signed: Geo Massey
Well Plugging Supervisor