

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 46-9

LOCATION SE SE NW

SEC. 21 TWP. 10 RGE. 20

Dry Hole          Abandoned Oil Well x Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. 1 Lease Hinkhouse

Operator Derby Oil Co Address Wichita, Kans

Field          County Rooks

Total Depth 3764 Feet.

Plugging Contractor Bert Self Pipe Pulling

Plugging Contractor's License No. 48

Address         

(Describe briefly the manner in which the well was plugged)

8 5/8" at 255' circulated with cement - 5 1/2" at 3760' with 100  
sax cement behind.

Filled with sand to 3750', set 4 sax cement with dump bailer,  
pulled 2854' 5 1/2" - mudded hole to 240', set rock and 15 sax cement,  
mud to 55', set rock and 10 sax cement to bottom cellar.

STATE OF KANSAS  
09-21-54  
CONSERVATION DIVISION

J. Elmer Petty  
District Conservation Agent

Date 9-15-54

**PLUGGING**  
FILE SEC 21 TWP 10 RGE 20  
BOOK PAGE 46 LINE 9