

15-051-22850-00-00

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051 - 22,850 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Green Oil Operation

Complete Address P.O. Box 503, Hays, Ks. 67601

Lease Name General Seitz "A" Well No. 1

Location SE NW NE Sec. 4 Twp. 12 Rge. 19 (East) (West)

County Ellis Total Depth 3700'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A XXX

Other well as hereinafter indicated     

Plugging Contractor Big Springs Drilling, Inc.

Address Box 8287 Munger Sta., 400 N. Woodlaun, #29 Wichita, Ks. License No. 67208

Operation Completed: Hour: 1:00 AM Day: 4 Month: March Year: 19 82

Plugging Operations attended by Agent?: All      Part      None XXX

The above well was plugged as follows:

8 5/8"-246' S.P. cuc. W/ 165 sacks common-2% gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-~~4~~% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot W/ drill stem W/ heavy mud between all plugs.

1st plug @ 780' W/ 70 sacks cement

2nd plug @ 250' W/ 40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 246' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Icy Roads-Weather Advrsory-Emergency travel only.

Signed: [Signature]  
Conservation Division Agent

31082  
9608-W

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 8 1982  
3-8-1982  
CONSERVATION DIVISION  
Wichita Kansas