

15-051-00575-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE SE NW

SEC. 4 TWP. 12 RGE. 19

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Merrill

Operator Artnell Co Address 533 Pet Bldg Wichita,

Field _____ County Ellis

Total Depth 3680 Feet.

Plugging Contractor Leben Drg Co & Sun Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 231' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at
700', displaced 25 sax cement through drill pipe, heavy mud to
210', set cementing plug and displaced 25 sax cement through drill
pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10
sax cement to bottom cellar.

District Conservation Agent

Date 8-4-57

8-6-1957

PLUGGING
FILE SEC 4 T 12 R 19W
BOOK PAGE 34 LINE 17