

15-051-01244-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
1-5-1960  
JAN 5 1960

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: SW NW SE Sec. 4 Twp. 12 Rge. 19 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3725

I have this date completed supervision of plugging of:

Lease Name: Nicholson Well No. 1

Operator's Full Name: Artnell Co

Complete Address: 533 Pet Bldg Wichita, Kans

Plugging Contractor: National Drg Co

Address: Wichita, Kans License No. \_\_\_\_\_

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 9AM Day 31 Month 12 Year 59

The above well was plugged as follows:

8 5/8" 245' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 600', displaced 20  
sax cement through drill pipe, heavy mud to 200', set plug and 15 sax cement  
heavy mud to 40', set plug, 1/2 sack hulls and 10 sax cement to bottom  
cellar.

Signed: Edna Healy  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED  
DATE 1/14/60  
INV. NO. 584-u