

15-051-20386-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-5-1969
FEB 5 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name A. Ainsworth

Complete Address: 222 Brown Bldg., Wichita, Kansas

Lease Name Evans Well No. 1

Location SW NW SW Sec. 20 Twp. 12 Rge. 18 (E) XX (W) XX

County Ellis Total Depth 3773

Abandoned Oil Well XX Gas Well XX Input Well XX SWD Well XX D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 10:30P Day 2 Month 2 Year 1969

The Above well was plugged as follows:

RTD 3773' 8 5/8 csg set at 213' CWC Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cement to base

of cellar. Plugged rat hole with 2 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ray T. Massey
Well Plugging Supervisor

DATE 2/6/69

INV. NO. 9293-W