

6 050146

API NUMBER 15-05124062

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 36, T. 12 S., R. 17 (NW)

2310 feet ^N from SE section line

3400 feet ^W from SE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7437

Lease Name Leikow Well # 1

Operator Name & Address E & B Company

County Ellis

Eddie Brungardt

Well Total Depth 3608 117.26 feet

Victoria Kans

Conductor Pipe: Size _____ feet

67671

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Revelon Drilling Co.

STATE CORPORATION COMMISSION
RECEIVED 5671
License Number 11-6-1984
NOV 06 1984
CONSERVATION DIVISION
Wichita, Kansas

Address Box 293 Russell Kans.

Company to plug at: Hour: _____ Day: _____ Month: _____

Plugging proposal received from Gene Augustine

(company name) Revelon Drilling Co. (phone) _____

were: Order 185 sac 5/80 poz mix 6% gel 3% cal cl 1st Flo cel - 1 sac hulls
8 5/8" cementing Plug.

Get pits circulate hole with heavy mud - spot all plugs
then drill pipe with heavy mud between all plugs, no fluid
loss. 1st Plug at 1300' - 25 sac - 2nd Plug 740' @ 100 sac w/ 1 sac flo cel - 260 sac
40' solid bridge 1 sac hulls 10 sac - 10 sac in Rat hole.
Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None Y

Operations Completed: Hour: 11a Day: 1 Month: Nov Year: 19 84

ACTUAL PLUGGING REPORT

1st Plug 1300' @ 25 sac cement.

2nd Plug 740' @ 100 sac cement + 1 sac flo cel

3rd Plug 260' @ 40 sac

4th Plug 40' with 8 5/8 Plug 1 sac hulls + 10 sac cementing to base of well

Rat Hole 10 sac

Remarks: Cemented by Allied
(If additional description is necessary, use BACK of this form.)

INVOICED (did/did not) observe this plugging.

DATE 11-6-84

Signed Gilbert P. Leiker
(TECHNICIAN)

INV. NO. 4641

DEC 07 1984

11-2-84
a