

15-051-23877-00-00

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23,877  
NW NE SE, Sec. 36, T 12 S, R 17 W/S  
2310 feet from N/S section line  
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9394

Lease Name Leikam Well # 1

Operator: Del Oil Company  
Name & Box 278  
Address Victoria, Ks. 67671

County Ellis

Well Total Depth 3615 feet 117.49

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Dreiling Oil Company License Number 5145 Rig Tag 535

Address Box 1000, Victoria, Ks. 67671

Company to plug at: Hour: Day: Month: Year: 19

VERBAL PLUGGING ORDERS GIVEN TO Pete Nalzsmith

(company name) (phone) 625-6336

were: Order 175 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 8 AM Day: 27 Month: May Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 1250' w/25 sks

2nd plug @ 680' w/80 sks 1 sk flo-cel

3rd plug @ 240' w/40 sks

4th plug @ 40' w/8 5/8" plug 1/2 sks hulls-10 sk

10 sks in Rat Hole 10 sks in Mouse Hole

Remarks: Cemented by Halliburton

RECEIVED  
STATE CORPORATION COMMISSION  
1-4-1984  
JUN 04 1984

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Gilbert P. Leiker (TECHNICIAN)

INVOICED

DATE 6-5-84

INV. NO. 1800

5-27