

1-21

15
R

15-051-20843-00-00

6 - 070980

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-20,843
S/2SESE /4 SEC. 31, 12 S, 17 W
330 feet from S section line
660 feet from E section line

Operator license# 8061 Lease Karlin well # 3

Operator: Oil Producers Inc. of Ks. County Ellis

Address: Box 8647 Well total depth 3648 feet
Wichita, Ks. 67208 Conductor Pipe: inch @ feet
Brad Siroky Surface pipe 8 5/8 inch @ 298 feet

118.56

Aband. oil well xx, Gas well , Input well , SWD , D & A

Plugging contractor: B. J. Services and Baker Pulling License#

Address: Hays, Ks. and Codell, Ks.

Company to plug at: Hour: AM Day: 21 Month: January Year: 92

Plugging proposal received from: Brad Siroky

Company: Oil Producers Inc. of Ks. phone: 316-681-0231

Were: 8 5/8 298ft. s.p. cwc w/220 sks cement; 4 1/2 casing set at 3624 w/125 sks cement. Perfs at 3352 - 3332. Casing good. 382 ft of tubing at bottom of hole. Proposal 375 sks 65/35 poz 8% gel and 5 sks hulls. Pump in with pump truck. Perf at 1300 and 720 ft. Run tubing to a minimum of 3000 ft. Spot and displace cement. Load both 4 1/2 casing and 4 1/2 x 8 5/8 annulus w/cement. Shut in under pressure.

RECEIVED
STATE CORPORATION COMMISSION
2-12-1992
12 1992
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All x], Parti], None]

Completed: Hour: 12:30PM, Day: 21, Month: January

Actual plugging report: Oil Producers ordered 275 sks 65/35 poz and 5 sks hulls. Pumped cement in with pump truck. Spotted & displaced with tubing. L. K. Wireline perforated 4 1/2 casing at 1300 and 720.
1. 2 3/8 tubing at 3000 ft. w/15 sks cement followed w/ 85 sks cement and 2 1/2 sks hulls mixed in. 2. 2 3/8 tubing at 1600 ft w/60 sks cement. Cement circ out of 4 1/2 casing. 3. Pumped 150 sks cmt in 4 1/2 8 5/8 annulus. Max pressure 300 psig. Shut in 150 psig. Squeezed 4 1/2 casing w/15 sks cement. Max pressure 600 psig. Shut in at 600 psig.

Remarks: B. J. Services
Condition of casing (in hole): GOOD x BAD Anhy. plug: YES NO
Bottom plug (in place): YES x, CALC , NO Dakota plug: YES x, NO
Plugged through TUBING x, CASING Elevation: GL

DATE 2-18-92 I did not observe the plugging.

Marion J. Schmidt
Marion J. Schmidt (agent)
Form CP-2/3

INV. NO. 3458K MAR 17 1992
1-21