

15-051-20904-00-00

6 070863

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-20,904-00-00

NE NE SE SEC. 31, T 12 S, R 17 WXB
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Karlin Well # 4

Operator: Oil Producers of Ks. Inc.
Name & Address: Box 8647
Wichita, Ks. 67208
John S. Weir

County Ellis 117.06
Well Total Depth 3602 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cement Baker Well Service License Number

Address Hays, Ks. Codell, Ks.

Company to plug at: Hour: AM Day: 8 Month: Oct. Year: 19 90

Plugging proposal received from Louis Kuhn

(company name) Oil Producers of Kansas Inc. (phone)

were: 8 5/8 249 ft. s.p. cwc w/220 sks. 5 1/2 casing set at 3600 ft. w/125 sks cement.

Casing poor. Elv. 2061. Anhy 1317 ft. Proposal. Perforate 5 1/2 casing at 1263

and 711. 400 sks 65/35 poz 8% gel and 8 sks hulls. Spot and displace with tubing.

Run tubing to a minimum of 2500 load 5 1/2 casing bottom to top. Also, load 5 1/2 x 8 5/8

annulus. Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 PM Day: 8th Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT Oil Producers ordered 400 sks 65/35 poz and 8 % gel and

8 sks hulls. Spotted and displaced with tubing. 2 3/8" tubing at 2500 ft w/150 sks cement

w/5sks hulls added in. 2 3/8 tubing at 1720 ft w/125 sks cement w/3 sks hulls. Cement cir

Pressured annulus with 60 sks cement. Max pressure 600 psig. Shut in at 500 psig.

Pressured 5 1/2 x 8 5/8 annulus w/60 sks cement. Max pressure 750 psig. Shut in at 500 psig.

OCT 15 1990
10-15-1990
CONSERVATION DIVISION

Remarks: By Halliburton Cement
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-19-90

10-8

JAN 10 1991

Signed Marion J. Schmidt (TECHNICIAN)