

9-7

4 060112

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-23,548

SW SE, SEC. 31, T 12 S, R 17 W/E

330 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Karlin Well # 5

Operator: Oil Producers Inc. of Ks.

County Ellis *112.95*

Name & Address P.O. Box 8647

Well Total Depth 3660 feet

Wichita, KS 67208.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 175

Abandoned Oil Well XXXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Co Tools License Number _____

Address _____

Company to plug at: Hour: 10:00AM Day: 7 Month: September Year: 19 90

Plugging proposal received from John Weir

(company name) Oil Producers Inc. of Ks (phone) 316-672-3440

were: Order 350 sxs. 65/35pos 8%gel and 500# hulls

Run minimum of 2000' of tubing.

Perf. 'at 1305' in Anhydrite.

Well had a prior squeeze from 1050' to surface in annulus with 300 sxs.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 7 Month: September Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" at 281', 5 1/2" at 3659'. Run tbg. to 2000' and

pmp 260 sxs. 65/35pos 8% gel and 500# hulls. Pulled tbg to 1000' and pmped

65 sxs. 65/35pos 8% gel until circ to surf. Pulled tbg. and tied onto csg.

and pmped 25 sxs. 65/35pos 8%gel. Max Press 500# SIP 250#.

SEP 11 1990
9-11-1990

Remarks: Halliburton Cementing

(if additional description is necessary, use BACK of this form.)

INVOICED

I (did XXXXXXXX observe this plugging.

DATE: SEP 10 1990

INV. NO. 29348

9-7 JAN 10 1990

Signed Herb Deines
(TECHNICIAN)

Herb Deines