

6 061754

1-13

163 KCCo/B

API NUMBER 15-

~~15~~-21,237-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W E S E - SW, SEC. 27, T. 10 S, R. 19 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

990 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6412

Lease Name Boy Home Well # 1

Operator: Sid Tomlinson

County Rooks 121.26

Name & Address Route 4 Box 7695

Well Total Depth 3731 P.B. 3710 et

Twin Falls, Id. 83301

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:30AM Day: 13 Month: Jan Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 250 sks 60/40 Poz 8% Gel 3% Cal Cl 5 sks Hulls.

Order 100 more sks of cement.

RECEIVED
STATE CORPORATION COMMISSION
1-26-89
JAN 25 1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:50PM Day: 13 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT 8 5/8" set at 253' w/165 sk. 4 1/2" set at 3729'
w/175 sks. Top perf at 3423'. Plugged bottom w/sand and 4 sks cement to 3375'. Shot pipe
three times and recovered 560'. Shot hole at any and pumped 35 sks down casing. Shot pipe
at 560' and circulated cement to surface. Pulled casing and hooked onto 8 5/8" and pressured
to 600 psi. Used 360 sks cement.

Remarks: By Halliburton
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck

INVOICED
DATE 1-30-89
INV. NO. 23820