

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22569-00-00
Spot: S2NESW Sec/Twnshp/Rge: 5-18S-9W
1550 feet from S Section Line, 2100 feet from W Section Line
Lease Name: PLOOG Well #: 2-5
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 33770
Op Name: ARES ENERGY, LTD
Address: 303 W WALL STE 900
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	389		185 SX CMT

108-88

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/26/2009 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: _____ Company: ALLIED CEMENTING Phone: _____

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 06/26/2008 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

PUMP 35 SX'S ~~THRU~~ DRILL PIPE @ 3249', PULL TO 1200' & PUMP 35 SXS, PULL TO 433' & PUMP 35 SXS, PULL TO 60' & CIRCULATE 25 SX'S TO 0'. ALL PLUGS EXCEPT 60' TO 0 WERE DISPLACED WITH DRILLING MUD. 15 SX'S INI RAT HOLE, AND 10 SX'S IN MOUSE HOLE.

Perfs:

NOV 06 2009
11-6-09
2010060441

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 23 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. ALLIED CEMENT TICKET #33034.

Plugged through: DP

District: 02

Signed Virgil Clothier
(TECHNICIAN)