

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21674-00-00
Spot: SESENE Sec/Twnshp/Rge: 10-16S-26W
2310 feet from N Section Line, 280 feet from E Section Line
Lease Name: LEVI Well #: 2
County: NESS Total Vertical Depth: 4553 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	321		WITH 200 SX CMT
PROD	5.5	4523	0	WITH 200 SX CMT 147.97

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2009 9:30 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: PUMP HULLS & CMT TO BOTTOM. RUN BOND LOG. PERFORATE & PUMP CASING VOLUME PLUS 80 SX CMT. IF IT DOES NOT CIRCULATE THEN 150 SX CMT DOWN BACKSIDE IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2009 2:20 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 40 SX CMT & 200# HULLS THEN 16 SX GEL TO BOTTOM. MAXIMUM PRESSURE 500#. RAN BOND LONG & FOUND CMT AT 1270'. PERFORATED AT 1175'. PUMP 190 SX CMT DOWN CASING. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 500#. DID NOT CIRCULATE. PUMPED 125 SX CMT DOWN BACKSIDE. PRESSURED TO 200#. SHUT IN PRESSURE 150#.

Perfs:

Top	Bot	Thru	Comments
4523	4553	OH	

INVOICED
DATE 11-6-09
NO. 2010060442

RECEIVED
SEP 28 2009

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

KCC WICHITA

Plugged through: CSG

District: 01

RECEIVED
SEP 15 2009
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)