

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20494-00-00  
Spot: SWSE Sec/Twnshp/Rge: 13-29S-33W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: WRIGHT TRUST Well #: 5  
County: HASKELL Total Vertical Depth: 5800 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1860		188.50
CIBP		5250		
SURF	8.625	1842		WITH 700 SX CMT
DVT		3317		WITH 300 SX CMT
PROD	4.5	5799	0	350 SX THIXET 250 SX LITE 50 SX COM

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/17/2009 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO Phone: (316) 772-8650

Proposed Plugging Method: CIBP @ 1870' WITH 2 SX CMT. PERFORATE 4 1/2" @ 1860'. PUMP 75 SX CMT. LET SET 2 HOURS. TAG CMT. PERFORATE @ 690'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/17/2009 12:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG SET CIBP @ 5250'. 2ND PLUG SET CIBP @ 1860'. PERFORATE @ 1855'. PUMP RATE 1/8 BBL @ 1200#. RE-PERFORATED @ 1500'. PUMPED 75 SX CMT & DISPLACED TO 1200' WITH HEAVY MUD. 3RD PLUG PERFORATE @ 350'. CIRCULATE CMT TO SURFACE WITH 75 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5360	5365		
5346	5350		
5332	5337		
5306	5310		

RECEIVED  
11-6-09  
2010060443

RECEIVED  
SEP 28 2009

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

KCC WICHITA

District: 01

RECEIVED

SEP 22 2009

KCC DODGE CITY

Signed

*Steve Durrant*

(TECHNICIAN)