

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20548-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 26-8S-19W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: VEVERKA Well #: 2
County: ROOKS Total Vertical Depth: 3419 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	205	0	w/unknown sxs cmt
PROD	4.5	3415	0	w/unknown sxs cmt

111.12

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/14/2009 2:30 PM
Plug Co. License No.: 33137 Plug Co. Name: GASCHLER WELL SERVICE LLC
Proposal Rcvd. from: KEN VEHIQUE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Got tubing and packer stuck in the hole after squeeze. Top of tubing at 1700'.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 09/14/2009 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report: Perfed at 1350' - 775' - 425' - 175'.
Ran tubing to 1700'.
Circulated with 145 sxs 60/40 pozmix - 4% gel cement.
Cement circulated out backside.
POOH. Topped off.

Perfs:
RECEIVED
SEP 25 2009
KCC WICHITA
11-6-09
2010060444

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: TBG

District: 04 Signed CASE MORRIS (TECHNICIAN)

SEP 23 2009

COLLINS & COLLINS

26-2-1977
NW NW NW

#2 VEVERKA

CONTR RED TIGER DRLG. CO. CTY ROOKS

GEOL ROGER WELTY FIELD MT. PLEASANT

E 1932 KB 11/3/74 CARD ISSUED 11/4/76 IP P 6 BOPD + 200 BWPD
ARB 3359-62

API 15-163-20,548

SMP	TOPS	DEPTH	DATUM
ANH	1335	+ 596	
TOP	2861	- 929	
HEEB	3073	-1141	
TOR	3097	-1165	
LKC	3110	-1178	
KC	3312	-1380	
ARB	3359	-1427	
RTD	3419	-1487	

8-5/8" 205, 4 1/2" 3415
DST (1) 3254-90/25-30, 10'M, SIP 355-106# FP 23-23# BHT 104°
DST (2) 3359-70/1", 80'MO, SIP 1032-1032#/30", FP 23-35# BHT 106°
DST (3) 3375-3419/20-, 540'MSW, 1090-NO FSIP, FP 142-260# BHT 109°
MICT - PF 3359-62, A 500, REC LD, POF

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS