

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20256-00-00
Spot: SENW Sec/Twnshp/Rge: 26-12S-16W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: FURTH Well #: 3
County: ELLIS Total Vertical Depth: 3467 feet

Operator License No.: 3956
Op Name: BRUNGARDT OIL AND LEASING INC.
Address: 529 E 14TH PO BOX 871
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	400	0	w/305 sxs cmt
L1	4.5	3200	3000	112.68
PROD	5.5	3454	0	w/75 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/22/2009 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY L. BRUNGARDT Company: BRUNGARDT OIL AND LEASING, I Phone: (785) 483-4975

Proposed Plugging Method: Ordered 330 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel.
DV'd at 1139' w/270 sxs - circulated - well has been squeezed.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2009 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

09/21/2009 - Express Well Service pulled into liner.
Tiger Perfing Company shot off liner at 3000'.
Express Well Service pulled 3000' of 4 1/2" liner.
09/22/2009 - RIH with tubing to 3000'.
Allied rigged to tubing and pumped 11 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1800'. Allied rigged to tubing and pumped 140 sxs cement with 300# hulls to circulate cement to pit area.
Pulled tubing - topped off 5 1/2" casing with 25 sxs cement.
Hole standing full.
Rigged to 8 5/8" casing - pumped 1/2 barrel.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3454	3467		Arbuckle

11-6-09
2010060445

RECEIVED
SEP 25 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38419.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

SEP 23 2009

KEWANEE OIL COMPANY #3 FURTH 26-12-16W
 WICHITA, KS. C SE NW
 Contr. PEEL BROS. Cty. ELLIS
 Geol. RAY YOUNG Pool. EMMERAN NE.
 E. 1981 GL. Cm. 5/31/68 Cp. 7/3/68 IP P 50BOPD + 14 BWPD
 ARB 3454-67
 API 15-051-20,256

LOG Tops	Depth	Datum	Csg.
			8-5/8" 400.54/305SX
			5-1/2" 3454.96/75SX
ANH	1123	+ 858	DST 3090-3120/1', 50' WM, BHP 841-866#/60", FP 18-23#
HEEB	3140	-1159	DST 3173-3205/1', 10' VSO&GCWM, 240' WM, BHP 968-986#/60", FP 18-78#
TOR	3162	-1181	DST 3278-95/45", 5' SOCM, FBHP 374#
LANS	3192	-1211	60", FP 18-21#
GOR	3442	-1461	DST 3336-66/1', 60' O&GCM, 60' HO&GCM, 60' HOC&SGCM, BHP 701/45" 684#/75", FP 25-41#
ARB	3455	-1474	DST 3452-60/1', 65' HOCM, BHP 979-60"-961#/75", FP 18-21#
			DST 3452-65 MIS-RUN
LTD	3467	-1486	DST 3455-65/1', 25' SMC0, 126' VS MCO, BHP 979-968#/75", FP 19-41#

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

CO, BL 5.1 BO + 2.2 BW 5 1/2 HRS NAT
 A 250: SWB LD. SWB 55.2 BO+7.8 BW