

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-20152-00-00
Spot: SESESW Sec/Twnshp/Rge: 7-31S-10E
330 feet from S Section Line, 2150 feet from W Section Line
Lease Name: WILSON ADALINE Well #: 1
County: ELK Total Vertical Depth: 2182 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1 BOX 1B2
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	99		
PROD	4.5	2175		70.92

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/31/2008 8:00 AM

Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: Perforate at 1000' and 550'. 50' plug a TD (2181'), 50' plug at 1000' and 550' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 12/31/2008 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated pipe at 1000' and 500'. Ran 2' tubing to 2181 gelled hole and spotted 10 sacks of cement. Pulled 2" up to 1000' spotted gell and pulled 2" up to 900'. Spotted 10 sacks of cement. Pulled 2" up to 600' and spotted 100# of gell. Pulled 2" up to 500' and circulated cement to surface. Pulled 2" and topped well off. A total of 200 sacks of cement were used to plug this well.

Perfs:

RECEIVED
SEP 28 2009
KCC WICHITA

RECEIVED
KCC DISTRICT #:

SEP 22 2009

AAS

CHANUTE, KS

11-6-09
2010060446

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)