

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20335-00-01
Spot: NESW Sec/Twnshp/Rge: 21-34S-21W
1999 feet from S Section Line, 3288 feet from E Section Line
Lease Name: BARBY Well #: 2-21
County: CLARK Total Vertical Depth: 5610 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4220		WITH 2 SX CMT
CIBP		4450		
SURF	13.38	324		WITH 325 SX CMT 182.33
COND	20	132		
	11 8.625	812		WITH 200 SX CMT
PROD	5.5	5375	2700	WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/16/2009 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4220' WITH 2 SX CMT. PLUG AT 880' WITH 15 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 50' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2009 11:45 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 4220' WITH 2 SX CMT. 1ST PLUG AT 880' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 50' WITH 20 SX CMT. CMT AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
5454	5462		
5425	5427		
5415	5417		
5396	5399		
5336	5340		
4265	4273		

11-6-09
2010060447
RECEIVED
SEP 28 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

KCC WICHITA
PJS

Plugged through: TBG

District: 01
RECEIVED
SEP 22 2009
KCC DODGE CITY

Signed Jerry W. Stapleton
PIR II (TECHNICIAN)