

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20425-00-00
Spot: NENESW Sec/Twnshp/Rge: 21-34S-21W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BARBY Well #: 3-21
County: CLARK Total Vertical Depth: 4400 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4220		WITH 2 SX CMT
SURF	8.625	854		WITH 200 SX CMT 143.00
COND	20	150		WITH 375 SX CMT
PROD	4.5	4392	3000	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2009 2:30 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4220' & 2 SX CMT. PLUG AT 870' WITH GEL WATER & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2009 3:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 4220' WITH 2 SX CMT. 1ST PLUG AT 880' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 55' WITH 25 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4270	4280		

11-6-09
2010060447

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

RECEIVED

SEP 28 2009

KCC WICHITA

District: 01

Signed

Jerry W. Stapleton

PIRT JI (TECHNICIAN)

RECEIVED

SEP 22 2009

KCC DODGE CITY