

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-04415-00-00
Spot: SESESE Sec/Twnshp/Rge: 4-18S-8W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: KRATZER Well #: 1
County: RICE Total Vertical Depth: 3270 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8	215		125 SX
PROD	5.5	3263		UNKNOWN 106.28

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/03/2009 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 983-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/03/2009 12:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3050' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1150', 800', AND 275'. RUN TUBING TO 1150' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 800' AND PUMP 35 SX'S CEMENT, PULL TUBING TO 275' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 115 SX'S.

Perfs:

11-6-09
2010060448

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 23 2009

Remarks: 60-40- POZ, 4% GEL. COPELAND TICKET #C-32894. LOG TECH OF KS TICKET #5817. CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)