

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20884-00-00
Spot: E2SWSWNE Sec/Twnshp/Rge: 16-34S-23W
2970 feet from S Section Line, 2265 feet from E Section Line
Lease Name: EUBANK - C Well #: 16
County: CLARK Total Vertical Depth: 5559 feet

Operator License No.: 33392
Op Name: KEITH F. WALKER OIL & GAS CO., LLC
Address: 219 STANLEY ST PO BOX 1725
ARDMORE, OK 73401

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5387		WITH 10 SX CMT
SURF	8.625	830		WITH 500 SX CMT
COND	13.38	192		WITH 275 SX CMT
PROD	4.5	5559	2004	WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/18/2009 9:30 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Revd. from: RIGO MANDRANO Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 435-3373

Proposed Plugging Method: SET CIBP @ 5400' & 10 SX CMT. PLUG AT 840' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/18/2009 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SET CIBP @ 5387' WITH 10 SX CMT. LOAD HOLE WITH MUD. 1ST PLUG AT 840' WITH 50 SX CMT. 2ND PLUG AT 304' WITH 50 SX CMT. 3RD PLUG PULL TO 60' & PUMP 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5448	5464		

11-6-09
2010060454

RECEIVED

SEP 28 2009

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY PHIL DOLLARD OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED

SEP 22 2009

KCC DODGE CITY

Signed

Jerry W. Stapleton
PIRTH

(TECHNICIAN)